Items of work	Per	Quantity
Kitchen block—concld.		
Teak-wood finials	Each	2
Silicate painting	Sqr.	5·88
Flooring with Cuddapah slabs over 3" concrete and cement painting	"	4·00
Flooring with Mangalore tiles	"	1·50
Burnt brick in chunam coping	R. ft.	24
Chunam painting	Sqr.	3·09
Constructing chimneys	Lump sum	2
Stables.		
Earthwork excavation	C. yd.	27
Burnt brick in mortar	C. ft.	1,097
Burnt brick in clay	"	1,099
Burnt stone slab 6" thick	S." ft.	111
Chunam plastering	Sqr.	25·29
White and colourwashing	"	25·29
Teakwood wrought and put up with wood oiling	C." ft.	129·72
Roofing with 1st class Mangalore tiles with teak reepers	Sqr.	8·08
Ridge tiles	R. ft.	39
Teakwood battened doors with frames 4"×3" with hinges lock and key	S. ft.	18
Teakwood battened ventilators	"	18
Teakwood windows	"	12
Teakwood gate with bolts, hinges, etc.	"	72
Teakwood ornamental eave board	R." ft.	119
Teakwood pendants	Each	4
Teakwood finials	"	2
Silicate painting	Sqr.	2·40
Flooring with Cuddapah slabs	"	·96
Chunam painting	"	1·55
Latrine.		
Earthwork excavation	C. yd.	3
Burnt brick in mortar	C. ft.	183
Burnt brick in clay	"	177
Burnt stone slabs 6" thick	S." ft.	2
Chunam plastering	Sqr.	5·33
White and colour washing	"	5·33
Cuddapah slab flooring on 3" concrete bed and cement painting	"	67
Burnt brick in chunam coping	R." ft.	40

Abstract Notification.

The attention of the public is invited to the advertisement in detail published in *Mysore Gazette*, dated 30th May 1918, calling for tenders for repairing the temple of Sri Mallikarjunaswami at Bettadapur, Hunsur Taluk.

Y. ASWATHANARAYANA RAO,
Executive Engineer.

No. 5. YEDATORE DIVISION.

Notice.

Notice is hereby given that a bill for work done by piece workers Yeerigadindal Subbaboyee and Muddle Koppal Puttasamachari conjointly on the "Deviation of Yelwal-Hassan road has been prepared by the Sub-Divisional Officer and submitted to this office with a report that the whereabouts of the parties are not known. It is therefore hereby notified that the parties should intimate their whereabouts to this office within two months from the date for needful action being taken in the matter, failing which, steps will be taken to credit the amount of the bill to "revenue".

B. N. ARADHYA,
Executive Engineer.

MYSORE HEADQUARTER RANGE.

Abstract Notification.

Reference is invited to the Notification calling for tenders for the construction of a swimming pond below the Kukkarahalli Tank Bund in Mysore, published in pages 477 and 478 of the *Mysore Gazette*, dated the 30th May 1918.

B. SUBBA RAO,
Sub-Assistant Engineer.

HASSAN DIVISION.

Dated 25th May 1918.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Hassan Division, up to 10th July 1918, for restoring Halwagal-Dodkere, Registered No. 120, Hassan Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1919.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Hassan between the hours of 11 A.M. and 5 P.M.